सत्यमेव जयते

INDIA NON JUDICIAL

1

Government of Karnataka

Rs. 200

e-Stamp

Certificate No.	:	IN-KA70523087059801S
Certificate Issued Date	:	19-Nov-2020 03:16 PM
Account Reference	:	NONACC (FI)/ kaksfcl08/ SANJAYNAGAR2/ KA-BA
Unique Doc. Reference	:	SUBIN-KAKAKSFCL08327355133188685
Purchased by	:	KARNATAKA MATERIAL TEST HOUSE PVT LTD
Description of Document	:	Article 12 Bond
Description	:	CIVIL WORK AGREEMENT
Consideration Price (Rs.)	:	0 (Zero)
First Party	:	EXECUTIVE ENGINEER BBMP
Second Party	:	KARNATAKA MATERIAL TEST HOUSE PVT LTD
Stamp Duty Paid By	:	KARNATAKA MATERIAL TEST HOUSE PVT LTD
Stamp Duty Amount(Rs.)	:	200 (Two Hundred only)

सत्यमेव जयते

KARNATAKA MATERIAL TEST HOUSE PVT LTD IN-KA70523087059801S RS. 200 19-NOV-2020 03:16 PM

Please write or type below this line

CONTRACT FOR CONSULTIN[illegible] SERVICES.

Agreement No: EE/YNK.D/AG/ 191 **/2020-21** **Dated:** 12-02-2021

This Contract is entered into on 12-02-2021 between **The Executive Engineer, Yelahanka Division BBMP, Bangalore – 560064.**

And

Sri B Narayanaswamy (M/s Karnataka Material Test House Pvt Ltd), #02, 3rd Main Road, Next to CIL B Block, Sanjayanagar, RMV 2nd Stage, Bangalore 560094.

Consultant

Executive Engineer
Yelahanka Division, BBMP

Statutory Alert:
1. The authenticity of this Stamp certificate should be verified at 'www.shcilestamp.com' or using e-Stamp Mobile App of Stock Holding. Any discrepancy in the details on this Certificate and as available on the website / Mobile App renders it invalid
2. The onus of checking the legitimacy is on the users of the certificate.
3. In case of any discrepancy please inform the Competent Authority.

KARNATAKA GOVERNMENT OF KARNATAKA GOVERNMENT OF KARNATAKA GOVERNMENT OF KARNATAKA GOVERNMENT OF KARNATAKA GOVERNMENT OF KARNATAKA

WHEREAS, the Client wishes to have the Consultant performing the services hereinafter referred to, and

WHEREAS, the Consultant is willing to perform these services, **Consultancy services for Supervision, Project Management and Quality Control for the work of Comprehensive Development of roads and drains at Sai Nagara Phase-I & II yelahanka 208,407, 707SFS, Attur village and chitra layout in Attur ward no-03 in yelahanka Division (PACKAGE NO -02)**

NOW THEREFORE THE PARTIES hereby agree as follows:

1. Services:

(i) The Consultant shall perform the services specified in Attachment A, "Terms of Reference and Scope of Services," which is made an integral part of this Contract ("The Services").

(ii) The Consultant shall provide the personnel listed in Attachment B, Consultant's Personnel" to perform the Services.

(iii) The Consultant shall submit to the Client the reports in the form and within the time periods specified in Attachment C, "Consultant's Reporting Obligations".

2. Term:

The Consultancy services for preparation of project report for the said project roads will be required till the compilation of the work.

3. Payment:

A. Ceiling: For Services rendered pursuant to Attachment A, the Client shall pay the Consultant an amount not to exceed **Rs.9,80,000-00/- (Rupees Nine Lakhs Eighty Thousand Only) inclusive of all taxes.** This amount has been established based on the understanding that it includes all of the Consultant's costs as well as any tax obligation that may be imposed on the Consultant. The Consultant has submitted Security deposit amount received **of Rs.49,000/- in the form of TDR Vide No:39828492073, Dated:26.11.2020 and same will valid until 26-05-2021 From State bank of India** Security deposit recovered from the Consultant shall be released only after approval of PMC without interest thereon as per tender document.

Consultant

Karnataka Material Test House Pvt. Ltd. Bangalore

Executive Engineer
Yelahanka Division, BBMP

4. NOW THEREFORE The Parties i.e., the Client and the Consultant hereby agree as follows.

The following Documents attached here to shall be deemed to form an Integral Part of this Contract.

a. The General Conditions of Contract (here in after called the "GC") as stated in the RFP Document.

b. The Special Conditions of Contract (hereinafter called the "SC") as stated in the RFP Document.

c. The Following Appendices.

Appendix A : Description of Services

As stated in the RFP Document.

Appendix B : Reporting Requirements

The Consultant shall submit the following Report in course of the Assignment and shall constitute the Basis for the Payment.

Sl No	Description	Submission in Time from the Commencement of Services	No of Copies
1	Inception Report covering Approach and Methodology	20th day from the Start Date	3
2	Monthly Progress Report	5th day of the every month	3
3	Completion Report and Maintenance Manual	30 days after Completion of the Works (Provisional Acceptance)	3
4	As Built Drawings Furnished by the Contractor	45 days after Completion of the Works (Provisional Acceptance)	6

The Consultant shall submit Soft Copy of the Reports as indicated above.

Appendix C : Key Personnel and Sub Consultant

As stated in the RFP Document.

Appendix D : Services and Facilities provided by the Client

As stated in the RFP Document.

Consultant

Executive Engineer
Yelahanka Division, BBMP

5. The Mutual Rights and Obligations of the Client and the Consultant shall be as set forth in the contract, in particular

a. The Consultant shall carry out the Services in accordance with the Provisions of the Contract; and

b. The Client shall make Payments to the Consultants in accordance with the following Schedule of Payment.

i. 5% of Contract Price: On Entering into Agreement and against Submission of Bank Guarantee of equivalent amount.
ii. 20% of Contract Price: On Achieving 20% of Physical Progress at Site.
iii. 20% of Contract Price: On Achieving 40% of Physical Progress at Site.
iv. 20% of Contract Price: On Achieving 60% of Physical Progress at Site.
v. 20% of Contract Price: On Achieving 80% of Physical Progress at Site.
vi. 10% of Contract Price: On Submission of Completion Report, Maintenance Manual and As Built Drawings.
vii. 5% of Contract Price: At the End of Defect Liability Period.

6. Payment Conditions:

Payment shall be made in Indian Rupees, Within 180 days of Receipt of the Invoice submitted by the Consultant.

7. Time Schedule:

The Contract Period for the Consultancy Services shall be till the completion of the main work and it will be effective from the Date the Contract is signed by both the Parties.

IN WITNESS WHEREOF, the Parties here to have caused this Contract to be signed in their respective names as of the day and year first above written.

1.

2.

Consultant

Executive Engineer
Yelahanka Division, BBMP

BRUHAT BANGALORE MAHANAGARA PALIKE

ATTACHMENT – "A" TERMS OF REFERENCES AND SCOPE OF SERVICES

1. Back Ground

Bruhat Bangalore Mahanagara Palike (BBMP) "the client" is desirous of obtaining **"Consultancy services for Supervision, Project Management and Quality Control for the work of Comprehensive Development of Roads and drains at Sai Nagara Phase-I & II Yelahanka 208, 407, 707 SFS, Attur village and Chitra layout in Attur ward no-03 in Yelahanka Division (Package -02)"**

BBMP Intends to procure the services of a Consulting firm to carry out the construction supervision of the works and quality control including the project management.

It is envisaged to form the Works contracts in a manner so that maintenance of the road and its appurtenances is the responsibility of the contractor for a period of three years after completing of the work.

2. Description of Assignment

The Consultants services shall consist of construction Supervision of Works, quality control and project management.

3. DETAILED SCOPE OF SERVICES OF CONSTRUCTION SUPERVISION AND MANAGEMENT SERVICES

3.1 Scope of Work

The Consultant shall perform the principal services outlined below as a part of responsibility for the supervision of the works. They shall provide the qualified professional staffs with relevant experience to carry out the assignments. The Services shall include but not be limited to the following:

Represent the interest of the BBMP vis-à-vis the Contractor in any manner related to the construction contract and the proper execution thereof.

a) Furnish for the use of the Contractor all necessary topographic survey data as required for setting out of all permanent and temporary works.
b) Review and recommend for approval the Contractor's work schedule or revision thereof and any such plans of programmes that the Contractor is obliged to furnish for approval. The Consultant shall also prepare and submit a disbursement schedule for approval.

Consultant

Executive Engineer
Yelahanka Division, BBMP

c) Assess the adequacy of all inputs such as material and labours provided by the Contractor and his methods of work in relation to the required rate of progress and when required, take appropriate action in order to expedite progress. Keep and regularly update a list of the Contractor's equipment (and its condition) to ensure compliance with the Contractor's commitment in his bid.

d) Inspect and evaluate all Contractor's installations, shops and warehouses and other accommodation to ensure compliance with the terms and conditions of contract.

e) Examine and make recommendations on all claims from the Contractor for extension of time, extra compensation, work or expenses or other similar matters.

f) Compute quantities of approval and accepted work and materials and check, certify and make recommendations on the Contractor's Running Bills and final payment certificates. All payments shall be checked and countersigned by the Consultant. All Bills for payment shall accompany with necessary quality control test reports as per reports as per clause 200 of MORT&H.

g) Prepare and submit weekly/ monthly reports on the progress of works. The contractor's performance, quality of works and the project's financial status and forecasts.

h) Propose and present for the approval any changes in the Contract Documents that may be deemed necessary for the completion of works including information on any effect the changes may have on the contract amount and the time of completion of the project and prepare all specifications and other details.

i) Provide legal advice on possible contractor's claims.

j) Inform on problems or potential problems which arise in connection with the works contract and make recommendations for possible solutions.

k) Maintain representatives at the site in such manner that adequate supervision of construction work is ascertained at all times when the Contractor is working. Maintain representative at the Hot Mix plant in such a manner that adequate quality control of material, mix Design and use of blended waste plastic is ascertained at all the times when the contractor is working and also more than one contractor is working in the package.

l) Provide timely assistance and direction to the Contractor in all matters, related to the interpretation of the Contractor Documents, ground survey controls, quality control testing and other matters related to contract compliance and progress of the project.

m) Organize the supervision of the works with proper allocation of responsibilities to the individual inspectors and also at last one engineer staff must be present at the plant to ensure the proper quality of the mix as per relevant standard and at last two (2) engineering staff must be present at the site during the execution of the work, to

Consultant

Executive Engineer
Yelahanka Division, BBMP

supervise the work to ensure effective execution. The presence of these staff shall be certified by the engineer in charge of the work and shall be submitted along with other reports.

n) Prepare and maintain inspection and engineering reports and records to adequately document the progress and performance of the works.

o) Review and approve the Contractor's working drawings, and drawings for temporary works.

p) Perform all survey measurements of completed or partial works where required determination of quantities.

q) Assure the receipts of and maintain as permanent records, all warrants under the terms of the Contract Documents for materials and equipment accepted and incorporated in the project. All local materials incorporated in their source are also to be approved and as – built drawings to be prepared for all works by the contractor.

r) Perform all laboratory and field testing of materials and products needed to assure that the quality as specified in the contract documents is attained.

s) Inspect the safety aspects of the construction and temporary works to ensure that reasonable measure have been taken to protect life and property.

t) Before the issuance of the certificate of provisional acceptance, the Consultant shall carry out the necessary inspection, specify and supervise and remedial works to be carried out and recommend upon completion the inspection with representatives of the Contracting Authority and assist in issuing the certificate of substantial completion.

u) Submit after review, to the Client one complete set of reproducible, revised contract drawings showing the "as constructed" project, to the extent requested by the Client and to the extent possible from information provided by the Contractor or otherwise patently visible.

v) Perform all other tasks not specifically mentioned above but which are necessary and essential to successfully supervise and control all construction activities in accordance with the terms of reference of the works contract.

w) Render services as project management consultant also to plan and for timely completion the project. The consultant shall examine the actual progress achieved vis-a-vis, the accepted programme on regular basis. If any shortfall is noticed, the consultant shall study the reasons for such shortfall with specific reference to the inadequacies in deployment of men, material and machinery at the site. The Consultant shall bring to the notice of the contractor, to provide adequate men, material and machinery that are absolutely essential to wipe off the accumulated shortfall over a reasonable time frame and also to prevent such occurrences of shortfall in future.

Consultant

Executive Engineer
Yelahanka Division, BBMP

x) Provide BBMP with all details of progress achieved vis-à-vis the accepted programme on regular basis. If there are repeated slippages between the actual progress and programme notwithstanding the action taken by the consultant as stipulated in clause 7.1 (sl) the consultant shall report to BBMP with all the facts and figures including reasons for such repeated slippages in progress. The consultant shall assist BBMP in issuing notices to the contractor for wiping off the accumulated shortfall within a reasonable time frame. The consultant shall also work out the penalties impossible as per the agreement and intimate to BBMP for taking necessary action.

y) To submit the test report conducted on construction materials and at site during execution of the work and after completion of the work like Mix Design, Bitumen grade test, test on aggregates, Bitumen content, temperature at plant and at site, density test, granular sub base, wet mix macadam, emulsion, R.C. Concrete, slabs, cobble stones tiles, steel, and other required and necessary test reports for all components of the project.

ATTACHMENT "B" – CONSULTANTS PERSONNEL

4. Key Professionals for the required Services for the package:

1) Resident Engineer (Team Leader) cum Senior Highway Engineer -1No.
2) Senior Materials / QC Engineer -1 No.

4.1 The minimum requirement or supporting staff for the services for each package is as follows:

Quality Control Engineer	- 1No.
Quantity Surveyor	- 1 No.
Site Engineers (Highway)	- 1 No.
Lab Technicians	- 2 No.

The Minimum required experiences and qualification are as per Clause 2.1 of Data sheet.

The Services of these key personnel / supporting staff shall be available full time. During the entire period of project construction.

4.2 Services during the Defects Liabilities/Maintenance Period as per tender condition.

During this period, the consultant shall undertake the following:

4.2.1 Inspection of roads periodically and report to the BBMP regarding status/defects observations in the road and any maintenance works to be carried out by the contractor.

Consultant

Executive Engineer
Yelahanka Division, BBMP

4.2.2 Inspection of works prior to the expiry of the Contractor's. three year defects liability/Maintenance period, preparation of a final deficiency list if required supervision of remedial works and recommendation to BBMP as to the date of the Final Inspection of Works.

4.2.3 Carrying out Final Inspection of Works together with representatives of the BBMP and the Contractor.

4.2.4 Preparation and issuance of the Defects Liability Certificate.

4.2.5 Preparation of Final Payment Certificate.

5. ATTACHMENT "C" CONSULTANTS REPORTING OBLIGATIONS

5.1 Contract Schedule

The Project Constructions Period Stipulated is eleven (11) calendar months. However the Consultancy services for Project Management Construction Supervision may be required for a period of 7 to 8 months.

5.2 Schedule of the Reports

The Consultant shall prepare and submit four (4) copies to BBMP of each of the following reports and documents in English.

Inception Report and QAP	- within 7 days after mobilization.
Weekly – Progress Reports	- By the end of each week except the week following the inception Report.
Monthly Progress Reports	- By the 5th of the each month.
Final Report (Provisional acceptance)	- One week after completion of the works.
Q.A Report	- Along with the R.A Bills.

5.3 Contents of Reports:

a. Inception Reports

The Inception Report shall cover the following

- Reviewing Contractor's mobilization and work plan.
- Setting out Guidelines for Administering, Monitoring and Evaluating project Progress.
- Mode of co-operation with the BBMP, the concerned E.E and any other related organization(s).

Consultant

Executive Engineer
Yelahanka Division, BBMP

- Quality Assurance Programme.
- Plant inspection and report.
- Pre-execution material testing reports.

b. Weekly Progress Reports

The Weekly Reports shall be brief and concise and provide means of closely, monitoring project progress and forecasting construction costs, and shall cover the following.

- Main activities, undertaken and events for the period and Progress Report
- On the activities of the Contractor and supervision staff.
- Monitoring and Evaluation of project progress.
- Project accounts, payments of approved bills, claims, certificates of payments and variation orders.
- Summary of consultant's observations/results on Quality Control tests.

c. Monthly Progress Reports: Monthly Progress Report summarizing activities and work progress achieved in the last months will be submitted in lieu of the weekly progress report for the week.

d. Final Report: On Completion of the Project, the Consultant shall prepare a final report which will form a comprehensive record of the construction works including any changes or modification designs, problems encountered and solutions recommended operational procedures expenses and variations.

All reports and documents relevant to the services, maps, field survey notes, computer programmes etc. shall become the property of the BBMP. The Consultant shall provide one reproducible copy each of constructional and as-built drawings.

Consultant

Executive Engineer
Yelahanka Division, BBMP